BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE

Office Of The Executive Engineer, Dasarahalli Division

SCHEDULE-B

NAME OF THE WORK: Construction and Improvements Of Culverts in in Ward No.13 in Shettyhalli Sub Division.

SI No	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods Asper the Directon Of Enggineer -in-charge of the work	Cum	623.70	170.92	Rupees One Hundred Seventy And Ninty Two Only
2	Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with all lead and lift Asper the Directon Of Enggineer -in-charge of the work	Cum	59.40	2263.10	Rupees Two Thousand Two Hundred Sixty Three and Ten Paise Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down sizegraded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	Cum	59.40	5159.02	Rupees Five Thousand One Hundred Fifty Nine And Two Paise only
4	Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mmand down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super piasticisers @ 3 litersconfirming to IS 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars,posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing,complete but excluding cost of reinforcement Asper the Directon Of Enggineer -in-charge of the work	Cum	160.38	6371.66	Rupees Six Thousand Three Hundred Seventy One And Sixty Six Paise Only
5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Asper the Directon Of Enggineer -in-charge of the work	Tonne	13.95	64243.42	Rupees Sixty Four Thousand Two Hundred Forty Three And Forty Two Paise Only

Signature Of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division

6	Providing and removing centering, shuttering, strutting,. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cilis and string courses cost of all materials, labour Asper the Directon Of Enggineer -in-charge of the work	Sqm	633.60	310.58	Rupees Three Hundred Ten And Fifty Eight Paise Only
7	Providing and laying Pre Cast Drain Cover slabs of 250mm thickness including cost of all materials, labour, curing, transportation,loading, unloading etc.,complete as per the direction of Engineer - In-Charge. (Data Rate enclosed) Asper the Directon Of Enggineer -in-charge of the work	Sqm	356.40	4931.00	Rupees Four Thousand Nine Hundred Thirty One Only

Signature Of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division